

Building Practice Note **ESM-05: Fire Hydrant System Testing**

This Practice Note provides guidance on the testing and maintenance of fire hydrant installations.

The context below provides guidance for:

- Required hydrant system performance
- Commissioning and testing – New installations
- Commissioning and testing – Alterations to existing installations
- Maintenance



The design, installation, and availability of required fire hydrants is essential to ensure fire protection of buildings and occupants.

Abbreviations & Definitions

The abbreviations and definitions set out below are for guidance only. They are not intended to vary those set out in the Building Act 1993 (Act), Building Regulations 2018 (Regulations) or the National Construction Code (NCC).

- **Act** – Building Act 1993
- **AS** – Australian Standard
- **BAB** – Building Appeals Board
- **BCA** – Building Code of Australia (Volume One of NCC)
- **DtS** – Deemed-to-Satisfy
- **NCC** – National Construction Code 2019
- **RBS** – Relevant Building Surveyor
- **Regulations** – Building Regulations 2018

Required hydrant system performance

Designers, installers, testers, owners, and the RBS all play a part in ensuring that a fire hydrant system is fully functional in the event of fire. To prevent the spread of fire it is vital that new installations and alterations to existing systems conform with the relevant legislation applicable at the time of installation.

To achieve compliance with AS 2419.1, all tests as nominated in Section 10 must be satisfactorily carried out. The RBS should ensure that independent testing has been carried out and that compliance with the testing requirements of the

Standard is demonstrated, or that the Chief Officer has granted consent under regulation 129 to non-compliance with some or all of the required testing. This must occur before issuing an occupancy permit or certificate of final inspection. Apart from visual inspection of the installation (hydrant and hose reel location, type and method of installation of pipework and installation adequacy), the following tests are required to confirm system integrity and hydraulic adequacy.

Hydrostatic test

Pipework is required to be hydrostatically tested to the greater of 1700 kPa or 1.5 times the highest working pressure to which the system will be subjected, for a period of at least 2 hours. A number of installations have failed this test, due mainly to inadequate or undersized flanges and thrust blocks, or poor workmanship.

Commissioning (flow) test

This test requires simultaneous discharge of the required number of the most hydraulically disadvantaged hydrants, each at not less than the required outlet pressure and flow, to confirm that the required minimum total flow rate can be achieved.

The test results must be adjusted to design pressure conditions in order to check compliance (refer to AS2419.1 Appendix F).

Clause 8.5.10 (Test Facility) requires provision for disposing of test water to a suitable drain. This is important when the system is subjected to full flow testing, nominally every 3 years. Clause 10.3 emphasises the need to dispose of water without damaging private or public property. Hydrants installed in buildings or on roofs are often difficult to test without discharging water onto adjacent properties. Fixed drainage systems will reduce the possibility of flood damage.

Booster connection and pump tests

Where a system incorporates a booster or a suction point from static storage, verification of performance is required. Pump pressure and flow tests must be conducted wherever pumps are installed.

Where boosters are connected in series with building pumps which allows for the connection of a fire brigade appliance in series with the inlet connection an additional test is to be undertaken. The most hydraulically disadvantage hydrant shall discharge water at the required. While maintaining the recorded flow rate the system shall be boosted to achieve an additional 300kPa at the hydrant outlet. The pressure on the building pump discharge pressure gauge at this condition shall not exceed the system design operating pressure as displayed at the booster.

The tests are carried out by independent testers, using pumps that adequately simulate the performance of a fire authority pump. Verification that reasonable vehicle access is available will also be required.

These tests also enable confirmation that the maximum friction loss of 150 kPa in the pipework between the booster connection and the most hydraulically disadvantaged hydrant is not exceeded.

Test criteria for new installations may not be appropriate for an existing installation. To ensure systems are adequate testing should be carried out in accordance with the pressures required when the system was installed. Older systems with existing pipework may fail if tested under current pressures. These systems should be tested in accordance with Appendix One or as required by the RBS.

Where alterations to an existing installation are carried out, the RBS should ensure that independent testing has been carried out and that it demonstrates compliance with appropriate test criteria, or that the Chief Officer have granted consent under regulation 129 to any non-compliance with some or all of the required testing. This process must be completed before issuing an occupancy permit or certificate of final inspection.

Where a new booster connection is installed, the test criteria applicable to a new system must be applied to the whole system served by the booster connection. Where an existing booster connection serves new pipework extended from existing pipework, only the new pipework must meet the test criteria applicable to a new system. However, to apply these test criteria to the new pipework, some existing pipework may need to be upgraded under an application for a building permit. Refer to Appendix 1 -Hydrostatic test.

Fabricated junctions occur in both copper and steel pipe systems. Early copper pipe systems used prefabricated joints and later systems were fabricated on-site. Fabricated steel pipe systems were typically above- ground systems and used square elbows. Where no test duration is specified in the Table above, the time should be sufficient to allow all joints in the system to be inspected and should not be less than 2 hours.

Some sources in the table above use terms such as 'no significant leakage' or 'no leakage'. In practice, it is very difficult to achieve complete water tightness. Leaks should be monitored, as they have the potential to affect the maintenance and reliability of the system. If the rate of leakage increases with time, the source of the leak must be located, and repair work carried out before system failure occurs.

If the leakage rate is constant and reduces with a reduction in pressure, the leak is likely to be through a valve bonnet, or similar. In this case, 'topping up' during a test to maintain the pressure is acceptable, provided that the leakage rate is less than 15 L/minute. If the hydrostatic test criteria applicable at the time of installation cannot be established, an alternative is to determine the working pressure by testing. This is done by multiplying the result by a factor of 1.5 to give a hydrostatic test pressure with a 50 per cent safety margin, which includes an allowance for water hammer caused by a sudden increase in pressure that a system may not handle.

Maintenance

Fire hydrant systems form part of a building's essential safety measures. They are required to be maintained in accordance with Part 15 of the Building Regulations 2018. Adequate testing and maintenance can highlight design and installation faults, leading to their correction and ensuring that the system is functional and reliable.

Clause 10 of AS 2419.1-2005 sets out details of the flow rate tests to be recorded. The RBS must require systems installed in accordance with this Standard to be maintained in accordance with AS 1851 as applicable at time of installation. All flow and hydrostatic tests should be undertaken in accordance with AS 2419.1 Section 10 (or the equivalent criteria applicable at the time the system was installed), at the recommended intervals.

Although clause 4.2 of AS 2419 requires the source of water supply for fire hydrants to be not less than that necessary to maintain minimum specified flow rates for a duration of not less than 4 hours, it is not uncommon for hydrant systems to be used for a much longer duration. A major fire could result in the hydrant system being in continuous use for a number of days before the fire is brought under control and therefore the purpose of system design, installation and testing is to produce a system that is fully functional in any fire situation.

Appendix 1: Hydrostatic test

Operation dates of legislation	Source	Hydrostatic test pressure requirements – greater of
1 May 2006 to present	AS 2419.1–2005 Published 26 November 2006. Referenced in Building Code of Australia 2006.	1700 kPa or 1.5 x highest working pressure for at least 2 hours
1 Nov 1994 to 30 April 2006	AS 2419.1–1994 Published 18 July 1994. Referenced in Building Code of Australia 1990, 1996, 2004 and 2005.	1700 kPa or 1.5 x highest working pressure for at least 2 hours.
8 April 1991 to 31 Oct 1994	AS 2419.1—1988 Published 17 June 1988. Referenced in Building Code of Australia 1990.	1400 kPa or 1.5 x highest working pressure for 2 hours.
1 Feb 1987 to 30 June 1994	Victoria Water Supply and Sewerage Plumbing Regulations 1986 (S.R. 330/1986)	System with fabricated branch junctions - 1700 kPa. Other pipework - 700 kPa or mains pressure.
29 June 1983 to 31 Jan 1987	Melbourne and Metropolitan Board of Works Act 1958 By-Law No. 193: Water Supply (S.R. 116/1983).	System with fabricated branch junctions - 1700 kPa. Other pipework - 700 kPa or mains pressure.
Not referenced in legislation	AS 2419–1980 Published 31 December 1980.	1400 kPa or 400 kPa greater than highest working pressure where the working pressure is greater than 1000 kPa.

Related Documentation

- AS 2419.1–2005 Fire hydrant installations—System design, installation, and commissioning
- Building Act 1993
- Building Regulations 2018
- Fact Sheet: Fire protection – testers: https://www.vba.vic.gov.au/__data/assets/pdf_file/0013/121351/Restricted-Classes-for-Routine-Servicing-of-Fire-Protection-Equipment-fact-sheet.pdf

Version History

- Version 2.0, published 28 June 2021, supersedes Practice Note 38: Fire hydrant and system design, installation, commissioning, and testing

Contact Us

If you have a technical enquiry, please email technicalenquiry@vba.vic.gov.au or call 1300 815 127.

Victorian Building Authority

Goods Shed North
733 Bourke Street
Docklands VIC 3008

www.vba.vic.gov.au

Copyright

© June 2021 Victorian Building Authority (VBA).

This Practice Note has been prepared and published by the VBA for general educational and information purposes only. This publication must not be copied, reproduced, published, adapted, or communicated by any person without the VBA's prior written consent or as permitted by the Copyright Act 1968 (Cth). The VBA makes no warranties or representations whatsoever about the accuracy, reliability, suitability, completeness or authenticity of any information or material contained in this resource. Any use or reliance on such information is at a person's own risk. The VBA accepts no liability whatsoever for any direct, indirect, or consequential loss or damage any person may suffer arising out of or in connection with the access or use of this resource (including any third-party material included in this resource).